



Packaging & Transport

**For Console Shipment
(Via Sea Freight)**

Assembly Inspection

- After the assembly of console is completed, the consoles are bolted onto wooden pallets.



Console On Pallet

- Each bay of console is bolted onto individual pallet



Console Label

- Every bay of console is labeled clearly according to the drawing layout.



Wrapping of Console

- Each bay of console is given three layers of PVC wrapping.
- This will prevent condensation inside the console.
- Prevent scratches incurred during the course of shipment.



Finish Wrapping

- After all consoles are wrapped, they are ready to be stuff into the container.



Start to Load

- When the container arrived, the console are loaded into the container.



Loading

- The consoles are carefully loaded into the container, each bay at a time.
- Extra care are taken to ensure the console is not dented during loading.



Layout in Container



- As the container will be subjected to shock and vibration, every bay is spaced to prevent knocking between console during transport stage.



Nailed onto Container

- Every bay is nailed onto the wooden floor of the container.



Nail Check

- The nails are checked to ensure that it will not come out during shipment.



Continue Loading

- The whole sequence of loading is repeated till the container is fully stuffed.



Container Layout Check

- After the container is fully stuffed, the container is check again for possible damage that can happen during the transport stage.



Final Inspection

- If necessary, additional packing or damping material is added to ensure consoles will arrived in pristine condition at the destination.
- Additional support items like touch up paint, coupling kits, special tools, etc are also packed into the container.



Ready to set Sail

- Now the container is ready to set sail.
- With all these precautionary measures taken, our console will arrive at destination in good condition.





Your reliable Partner for

19" Rack and Console System